



RAPIDCAST TOOL LIST

EFCO recommends the following tools and materials for assembling and cycling EFCO equipment. This list of tools is based on information obtained at a similar jobsite by an EFCO Field Supervisor and is not intended to be all-inclusive. The tools and materials needed for a project vary depending on the region or country. Having these items readily available will help increase the productivity at your jobsite. Many of these tools are available from EFCO and can be purchased by contacting your local EFCO Territory Manager or through your EFCO ONLINE account.

RECOMMENDED TOOLS AND QUANTITIES FOR A CREW SIZE OF 4-6 WORKERS

QUANTITY **CARPENTER'S TOOLS**

- 1 CHALK BOX (PER WORKER)
- 1 HAMMER (PER WORKER)
- 1 PENCIL (PER WORKER)
- 1 RAZOR KNIFE (PER WORKER)
- 1 TAPE MEASURE (PER WORKER)

QUANTITY **HAND TOOLS**

- 1 4' LEVEL OR PLUMB BOB
- 1 3 LB SLEDGE HAMMER (AS REQUIRED)
- 1 FORM SCRAPER (PLASTIC)
- 1 LARGE PRY BAR - **10458**

QUANTITY **POWER TOOLS**

- 1 1/2" DRIVE DRILL
- 2 1/2" DRIVE IMPACT GUN
- 1 CONCRETE HAMMER DRILL
- 1 CIRCULAR SAW

QUANTITY **SOCKETS, RATCHETS & WRENCHES**

- 1 1/2" DRIVE SPUD RATCHET (PER WORKER) - **55889**
- 1 1/2" DRIVE 1-1/4" SOCKET (PER WORKER) - **42889**
- 1 1-1/8" OPEN END WRENCH (PER WORKER AS REQUIRED)
- 1 1/2" DRIVE 12" SOCKET EXTENSION
- 1 1-1/4" SPUD WRENCH (PER WORKER) - **51889/52889 (BENT)**
- 1 LARGE PIPE WRENCH - **35889**

QUANTITY **ANCHORS, FASTENERS & BITS**

- CONCRETE ANCHORS (AS REQUIRED)
- 2 13/16" SPADE DRILL BIT
- 2 1/4" STEEL DRILL BITS FOR FACE SHEET ATTACHMENTS
- CONCRETE DRILL BITS (AS REQUIRED)
- FASTENERS FOR SCAFFOLD PLANKING & HAND RAIL (AS REQUIRED)
- 1 PHILLIPS DRILL DRIVER #2 AND #3

QUANTITY **MISCELLANEOUS**

- 2 X 4 HANDRAIL MATERIALS (AS REQUIRED)
- 2 EXTENSION CORD
- 1 FORM OIL SPRAYER
- FORM OIL (AS REQUIRED) - **33894 (5 GALS) 35894 (55 GALS)**
- BULK HEAD MATERIAL (AS REQUIRED)
- SCAFFOLD PLANKING (AS REQUIRED)
- 1 STRAP AND STRING CUTTER - **32889**

